

CAMBRIDGE

ELEVATING

JOURNEY (LULA) INSTALLATION GUIDE

TECHNICAL SUPPORT:

Call or Text: 866-209-3421

Technical Information website:

cambridgeelevating.com/technicians/

Email: partsorders@cambridgeelevating.com

Refer to OLS Operator manual, Virginia manual, Virginia drawings for your project, hoistway layout, and CE connection drawings for details.

Preparation

- Pre-install site check
- Plan machine room
- Plan conduit/cable tray
Note: using the conduit entries in the bottom of the controller box can interfere with the installation of the UPS (battery backup unit).
- Plan hydraulic lines

Running Sling

- Mark the rail bracket centerline and height of each bracket on the rail wall as per the hoistway layout drawings.
- Choose method for mounting rail brackets depending on wall type and engineering specifications.
- Plan/prepare to work safely in the hoistway
- Rail brackets
 - Align each bracket using the height and centerline markings
 - Install a bolt loosely in the center hole
 - Level
 - Attach to rail wall
- Sliders
Note: each slider is installed with the V notch up and towards the inside of the rail bracket and the slider needs to be square to the wall.
 - Top rail bracket left slider
 - Position slider with a ½ inch overhang on the inside, the V notch 6 inches from the wall and square to the wall, drop plumb line over the inside edge through the center of the V notch.
 - Bottom rail bracket left slider
 - Touch line at V, readjust top if necessary, tighten, tie off line at center of V notch

- Remaining rail brackets left sliders
 - Touch line at V and tighten
- Top rail bracket right slider
 - Repeat as per top left
 - **Set the distance between the left and right sliders to 32 5/8th inches**
- Bottom rail bracket right slider
 - **Set the distance between the left and right sliders to 32 5/8th inches**
 - Touch line at V
 - Tie off line at V
- Remaining rail brackets right sliders
 - **Set the distance between the left and right sliders to 32 5/8th inches**
 - Touch the plumb line at V
- Baseplate
 - Must be level and between the rails
- Right side rail
 - Work bottom up, tongue up, grove down, short rail at top, refer to elevation drawing.
 - The rail should be centered on the slider and plumb if the sliders were installed correctly. If the wall is plumb the rail center to rail wall distance should remain 6 inches.
- Jack-post
 - Slider face to wall = approximately 4 inches (if the wall is plumb and true)
 - Install jack-post, plumb and true
 - Secure with U-bolt
- Cylinder (90mm assumed) see hoistway layout for size.
 - Slider face to wall = 3 7/16th inches
 - Install U-bolt but leave loose until plumbed
 - Install line rupture valve onto the cylinder
 - ***preset the line rupture valve**
 - **Loosen lock nut, turn adjustment all the way out, then 2 turns in, then tighten lock nut.**
- Sling
 - Lock shackles up with vice grips
 - Adjust main blue rollers out
 - If necessary, adjust side rollers
 - Engage sling with the right rail
 - Align with the left rail location
- Sling cross piece
 - Attach so that it is flush at the top
- Left side rail
 - Insert rail through the sling rollers and through the safeties & lower rollers
 - Work bottom up, tongue up, grove down, short rail will normally go at top (if any)
Refer to elevation drawing.
 - ***Rail center to wall = 6 inches**
 - ***DBG = 27 15/16th inches**

- Hydraulic lines
 - Keep inside of lines tank valve and fittings clean
 - Rubber hose recommended in machine room to prevent vibration transfer.
 - Turn cylinder so the line rupture valve is near the rail wall at the 1 o'clock position
 - Tighten the U-bolt holding the cylinder
- Hydraulic drain line
 - Attach plastic 90° fitting
 - Run line to pit and into a 4L container.
- Sheave
 - Remove cylinder shipping bracket and reinstall the cap screw
 - Remove the bottom plate from sheave
 - Attach bottom plate to the cylinder with the large bolt
 - Attach sheave to the bottom plate
 - 1/16th inch gap between each shoe and the rail
 - Make sure sheave assembly is parallel to rails.
- Ropes to sling
 - Leave room to adjust at shackles, install rope clips
- Main controller and HPU connections
 - Incoming motor power
 - Incoming lighting power
 - Controller to power unit power connections using BX or pipe
 - Controller to power unit control connections using 19c cable
 - Connect remote
 - *The power unit is preset and tested, major adjustments should not be necessary**
 - *Do not remove factory yellow jumpers at this time**
- Bleed air from cylinder
- Pre-stroke as per layout drawings
- Manually Lift sling to level with the lowest floor and block in place
- Ropes to jack post
 - Leave room to adjust shackles, do not install clips
- Sling extensions
- Adjust sling rollers
 - Do not adjust the yellow/white rollers (green paint mark should be out)
 - All blue rollers should touch rail lightly but still turn by hand
- Cab floor
 - Locate the floor based on the layout drawings
 - Secure floor to the sling
- Adjust safeties
 - Should be evenly spaced front to back
 - Use brake setting shim tool to set the roller
- Test the safeties
- Remove scaffolding
- Testing the travel of the sling
- Confirm clearances and door centerlines

Cab and Electrical

- Assemble cab
- Adjust cab so it is level, true and square
- Attach cab to sling
- Install hoistway wiring
- Install the Pit E-stop switch
- Install the call stations
- Install and set the limit switches
 - Top normal limit – activate 2 inches above level
 - Top slowdown limit – activate 1 inch above level
 - Hoistway access – activate cartop at top flr
 - Inspection limit –before top prop hits
 - Bottom slowdown – activate 1 inch below bottom floor
 - Bottom normal limit – activate 2 inches below bottom floor
- Cartop electrical
 - Chose position so the provided cables reach everything they need to connect to.
- Install COP and make connections
- Tape, tape reader and magnets
 - Use CE magnet drawing in the electrical details book
- Travel cable
- Running in inspection
 - Try with all jumpers still in

Cab gate(s)

- OLS (Victory) gate operator
- Install car gate panels and light curtains (screens)

Note: the landing and Car door panels differ

Landing doors

- Install landing door frames
- Install landing door panels
- Install fire gibbs

Finishing touches and testing

- Install fascia
- Running in auto
 - Confirm all travel and hoistway wiring
 - Confirm cab is mid hoistway
 - All magnets installed
 - All yellow jumpers removed except fire recall ones (S1 to 82 and S1 to 82M)
 - Service off at controller and cartop
 - Remote removed
 - Hoistway access off
 - Safety cct. Confirm 120vac at 1,2,3,4,5 and 6 Refer to Virginia drawings page R1
 - Limit SWs, confirm 120vac at 14,16,18, and 19 Refer to Virginia drawings page R2
 - Inspection circuit, confirm 120vac at 86,23x, 23y, 34y, and 23. INX relay should be on

- Run elevator
 - Adjust magnets as required
 - Test and adjust door operator(s)
 - Test and adjust landing doors
- Connect fire recall to a fire alarm system
 - S1, 82, 82M, 82F
- Test fire recall
- Test hoistway access
- Handrail(s)
- Final cleaning
- Adjust up movement
- Adjust down movement
- Test the low-pressure and the slack rope switch
- Test the line rupture valve
- Test the pressure release valve
- Program and test the telephone
- Test fan
- Install data tags
- Install stickers
- Landing frame brail tags
- Power failure test
- **Pre-inspection before Inspector**
- Inspection
- Customer training

3 Phase Power

If the phase monitor led is red –switch the wires with the push on connectors on the L1 and L2 terminals **on the phase monitor**.

If the motor sounds like it running backwards – switch the T1 and T2 wires in the main controller on the large terminals in the controller.

Setup and Adjustment of the Cambridge Elevating Hydraulic Power Unit.

Adjustment #1 (BP) – Up Delay

FUNCTION- Determines the length of the delay from pump start to car movement.

PRESET- Adjust in till click is heard then 3 turns out.

OPERATION- Turn in (CW) for less delay.

SETTING– Adjust so that the delay is approximately 1 second.

Adjustment #2 (UA) – Up Acceleration

FUNCTION- Determines how long it takes the elevator to reach full speed from a stop.

PRESET- Gently turn in (CW) until stop then turn out (CCW) one and a half turns.

OPERATION- Turning in (CW) will cause the elevator to take longer to reach full speed.

SETTING- Adjust so that car takes 2 seconds to reach full speed

Adjustment #3 (UD) – Up Full Speed Deceleration.

FUNCTION- Determines how quickly the car slows down to levelling speed.

PRESET- Gently turn in (CW) until stop then turn out (CCW) one and a half turns.

OPERATION- Turning in (CW) will increase the time it takes to slow down to levelling speed from full speed.

SETTING- Adjust so that the transition to levelling speed is quick but not uncomfortable (1 to 2 seconds).

Adjustment #4 (UL) – Up Levelling Speed.

FUNCTION- Determines levelling speed in the up direction.

PRESET- Adjust until screw is flush with casing.

OPERATION- Turning in will decrease the levelling speed.

SETTING- Adjust so that the levelling speed is approximately 8-10 feet per minute (1.5 to 2 inches in per second). The best way to set this is to turn off the high-speed switch located on the main controller board.

Adjustment #5 (US) – Up Levelling Speed Deceleration

FUNCTION- Determines how quickly the elevator stops

PRESET- Turn all the way out

Adjustment #6 (DA) – Down Acceleration

Note: Adjustment #6 can be affected by adjustment #8.

FUNCTION- Determines how long it takes the elevator to reach full speed from a stop.

PRESET- Gently turn in (CW) until stop then turn out (CCW) 1 turn.

OPERATION- Turning in (CW) will cause the elevator to take longer to reach full speed.

SETTING- Car should take 2 seconds to reach full speed.

Adjustment #7 (DF) – Down full speed

FUNCTION- Determines the car speed in the down direction.

PRESET- Adjust until screw is flush with casing.

OPERATION- Turn in to reduce the down speed.

SETTING- Adjust so that car travels up & down at the same speed

Adjustment #8 (DD) – Down deceleration

Note: Adjustment #8 can affect adjustment #6

FUNCTION- Determines how quickly the elevator transitions from full speed to levelling speed and from levelling speed to a stop.

PRESET- Gently turn in (CW) until stop turn out (CCW) 3 turns

OPERATION- Turn in to increase time it takes to slow

SETTING- Adjust for a smooth stop but no coasting

Adjustment #9 (DL) – Down Levelling speed

FUNCTION- Determines the speed of the car when traveling down in levelling speed.

PRESET- Adjust until screw is flush with casing.

OPERATION- Turn in to reduce the levelling speed.

SETTING- Adjust so that the levelling speed is approximately 10 feet per minute (2 inches in per second).

How to get the elevator out of the pit

NOTE: The Blain valve will not allow the contactors alone to raise the elevator.

- Jumper terminal #1 to terminal #6
- Jumper terminal #33 to terminal #35
- Push in both contactors till the elevator moves up
- Remove the jumpers